


Achieving the Green Dream
September 11-12, 2012
Sydney


Reducing carbon emissions provides other benefits including reduced operating costs

John Penny MAIRAH QCxP



AIRAH


Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)



Achieving the Green Dream
September 11-12, 2012
Sydney

Why existing buildings?

- lots of existing buildings
- all have opportunities
- benefits range from less than a month to one year economic payback
- helps identify capital and rehab projects with economic payback from one to 20 years




AIRAH

Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)

Case Study: 45 Clarence



Existing Building



Model



Achieving the Green Dream | Sydney | September 11-12 | Back to basics

Where do we begin?



- Assessment/Pre-investigation
- Owner's Project Requirements



Achieving the Green Dream | Sydney | September 11-12 | Back to basics

Pre Design Phase

Owner's Project Requirements

Goals

- Upgrade from 3.25 to 4.5 stars by mid 2012
- Retain A grade office
- Integrated project team
- Optimize what exists, without significant replacement
- Avoid redesign of conventional systems
- Back to basics scheme preferred
- Incentive from Green Building Funding



September 11-12, 2012
Sydney



Achieving the Green Dream | Sydney | September 11-12 | Back to basics


Pre Design Phase

Energy Efficiency Initiatives


Engineering Plant & Electronic Systems

- Heating, cooling and ventilation
- Building management & control
- Hot water
- Lighting systems
- Utilities metering

(Building envelope required only minor aesthetic upgrades)



September 11-12, 2012
Sydney




Achieving the Green Dream | Sydney | September 11-12 | Back to basics

Investigation Phase

Analysis of Options

Example of Options Analysed

- 3 Existing Trane Chillers
- 2 Powerpax + 1 Existing
- 3 New Powerpax Seq'ce
- 3 New Trane Parallel
- 3 New Powerpax Parallel
- 3 New York High Eff
- By changing from 800 + 1695 + 1695 kW to 590 + 1800 + 1800 kW
- Existing COP 3.98 - 5.5
- New COP 6.05 - 13.92




SOLUTION 11 TEST LOAD FLOW RATE TEMPERATURE W & T TORQUE CALCULATOR									
Flow Rate (m³/s)	Flow Rate (GPM)	Temp (°C)	Temp (°F)	Power (kW)	Power (HP)	Torque (Nm)	Torque (ft-lb)	Efficiency (%)	Notes
0.00	0.00	10.0	50.0	0.00	0.00	0.00	0.00	0.00	
0.05	1.35	10.0	50.0	0.05	0.07	0.00	0.00	0.00	
0.10	2.71	10.0	50.0	0.10	0.13	0.00	0.00	0.00	
0.15	4.06	10.0	50.0	0.15	0.20	0.00	0.00	0.00	
0.20	5.42	10.0	50.0	0.20	0.27	0.00	0.00	0.00	
0.25	6.78	10.0	50.0	0.25	0.33	0.00	0.00	0.00	
0.30	8.13	10.0	50.0	0.30	0.40	0.00	0.00	0.00	
0.35	9.49	10.0	50.0	0.35	0.47	0.00	0.00	0.00	
0.40	10.84	10.0	50.0	0.40	0.54	0.00	0.00	0.00	
0.45	12.20	10.0	50.0	0.45	0.61	0.00	0.00	0.00	
0.50	13.55	10.0	50.0	0.50	0.68	0.00	0.00	0.00	
0.55	14.91	10.0	50.0	0.55	0.75	0.00	0.00	0.00	
0.60	16.26	10.0	50.0	0.60	0.82	0.00	0.00	0.00	
0.65	17.62	10.0	50.0	0.65	0.89	0.00	0.00	0.00	
0.70	18.97	10.0	50.0	0.70	0.96	0.00	0.00	0.00	
0.75	20.33	10.0	50.0	0.75	1.03	0.00	0.00	0.00	
0.80	21.68	10.0	50.0	0.80	1.10	0.00	0.00	0.00	
0.85	23.04	10.0	50.0	0.85	1.17	0.00	0.00	0.00	
0.90	24.39	10.0	50.0	0.90	1.24	0.00	0.00	0.00	
0.95	25.75	10.0	50.0	0.95	1.31	0.00	0.00	0.00	
1.00	27.10	10.0	50.0	1.00	1.38	0.00	0.00	0.00	

Page 3 Page 35

600-700 MWhr Saving pa before safety factor

Detailed Analysis

Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)



Implementation

Understand limitations on site



Chiller plant behind neighbouring building, walls and plenum

Problematic access for crane access due to neighbouring building



Goods lift dimensions




Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)

Implementation

Operating System

- integrated project team
- quality focused commissioning process with three step verification
- prescriptive technical specification with functional requirements to achieve the owner's project requirements
- lesson learned: PM needed to be on site more frequently



Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)

Implementation

Engineering Initiatives

Heating, Cooling & Ventilation Plant

- single chiller replacement (later upgraded to all)

- variable speed drive replacements and additional units for pumping systems
- boiler replacement (**later deleted**)
- lift motor room A/C
- air handler new heating coils and rationalization of local reheating (**later deleted**)
- hydronic systems test and balancing
- repairs and maintenance of VAV air terminal unit (nearly 650 units)
- repairs to air handler economy & min OA dampers

Lighting systems

- office floor rezoning and switching (**deferred**)
- Foyer
- Lift lobbies
- Car park
- Toilets

Building Management & Control System

- workstation and software upgrade with extensive data logging and trending facilities
- main plant controller and network upgrade
- new CO2/VOC demand ventilation control
- upgrade air handler outdoor ventilation
- upgrade car park ventilation control
- retain working VAV air terminal unit controllers
- verify existing sensors & actuators

Other

- solar boosted hot water units
- sub metering of main switchboard, lift machinery and mechanical plant
- gas metering of hot water and heating water
- sub metering water consumption
- electrical power factor correction



Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)

Schedule Requirements



Achieving the Green Dream
September 11-12, 2012
Sydney


Activity	Finish Date
Assessment/Pre Investigation	Dec 2009
Strategic Improvement Plan	March 2010
Tender Specification & Drawings	June 2010
Implementation starts on site	Nov 2010
Implementation finishes on site	June 2011
Functional Performance Testing	July 2011
NABERS Energy Rating Assessment	May 2012



Very tight !

Achieving the Green Dream | Sydney | September 11-12 | Back to basics


Cost & Benefits




Achieving the Green Dream
September 11-12, 2012
Sydney

Financial July 2012

Return on investment (ROI) from energy and operational savings is > 15%.




Year	Cumulative Cash Flow
Today	-\$3,350,000.00
End of YR 1	-\$2,766,000.00
End of YR 2	-\$2,210,700.00
End of YR 3	-\$1,623,304.40
End of YR 4	-\$1,025,413.09
End of YR 5	-\$414,923.35
End of YR 6	\$207,780.22
End of YR 7	\$842,938.83
End of YR 8	\$1,490,794.64
End of YR 9	\$2,151,620.44
End of YR 10	\$2,825,642.44



Positive in 6th year

Achieving the Green Dream | Sydney | September 11-12 | Back to basics




Benefits


Energy Rating
Project goal was NABERS 4.5 stars
Delivered 5 stars in 1st year of operation with zero green energy

Carbon Emissions reduction
Goal of 37% was aggressive - delivered 43% carbon savings & energy savings of 50% in 1st year

Electrical Peak Demand Reduction
A saving of 39% over last 12 months - a true measure of deferring investment on the grid



Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)




Benefits

Occupant Comfort Index

Defined as the percentage of operating hours spent within a recommended temperature range. ASHRAE Standard 55-2004 recommends a range of 20-26°C. 45 Clarence set a target of 95% within 20-25°C. Temperature is measured for each zone and an overall index is provided for the whole building.

- Achieved 90% reduction in requests & issues from occupants
- Productivity benefits from these comfort levels are suggested to be many times the energy savings



Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)


Benefits

Occupant Comfort Report - July 2012



Name	Status	Comfort Index	Time High	Time Low
Total Building	●	98%	0.82%	0.91%

Zone Issues – July 2012




Name	Status	Comfort Index	Time High	Time Low
VAV.L03-E1	●	78%	0%	22%
VAV.L04-CW2	●	43%	57%	0%
VAV.L04-W3	●	86%	0%	14%
VAV.L11-CE3	●	28%	72%	0%
VAV.L11-N1	●	65%	0%	35%
VAV.L24-W3	●	0%	100%	0%
VAV.L25-CW5	●	0%	100%	0%
VAV.L25-N4	●	89%	11%	0%
VAV.L27-S1	●	90%	0%	10%
VAV.L28-CN2	●	0%	0%	100%
VAV.L28-CW2	●	85%	15%	0%
VAV.L28-W1	●	0%	0%	100%
VAV.L16-N3	●	0%	0%	100%







Achieving the Green Dream | Sydney | September 11-12 | Back to basics

Carbon Emission Savings




Achieving the Green Dream | Sydney | September 11-12 | Back to basics






Continuous Improvement Current Proposals



- tenant supplementary A/C heat rejection
- extend system performance tracking
- peak electrical demand control



Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)

Acknowledgments




“A pleasing aspect of the project and key driver in its success, was the collaboration and respect shown amongst the key contractors, Arup’s and the DEXUS team”, Paul Wall DEXUS Property Group

DEXUS Property Group
 Paul Wall - CapEx and Energy Manager
 Craig Brighton - Project Manager
 Robert MacKay – Senior Building Services
 Stephen Beaver - Building Manager

ARUP – Project Manager, Engineer & Commissioning
 Eric Serret – Project Manager
 Kate McAlpine – Controls Specialist /Technical Project Manager
 John Penny – Commissioning Authority
 Jeffrey Van Zetten – Energy Modelling, Hydronic Test & Balancing



Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)




Haden – Mechanical Services
 Ron Burke -Site Manager
 Ivo Grego - Commissioning
 Tom Astalosh - Engineering
 Carlos Martinez - Maintenance

Allworx Electrical
 Stephen Bruen, Project Manager
 Graeme Simpson, Electrical Site Foreman
 Dermot Minihan, Electrician
 Ciaran Needham, Electrician
 Jay Collet: Apprentice
 Andrew Hill: Apprentice

Haden Sub-Contractors:
 Austpipe
 Terry's Electrical Services
 Sika Services
 Interchillers (Powerpax)
 GnT Insulations
 Corellian (Riggin and demolition)

Greenstar Automation
 Zelko Rezo
 Ian Adams
 Graham Lee
 Robert Velk (Controls Overview)

A champion team will always win over a team of champions



Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)



An Australian Government Initiative



AusIndustryTM
 BUILDING BUSINESS • POWERING PRODUCTIVITY



Achieving the Green Dream | Sydney | September 11-12 | [Back to basics](#)